

ONGRID Solar Plant 5.00 kWp

01 September 2026

Project summary

System Type	ONGRID
Plant Capacity	5.00kW
Total Area Covered (Sq. Ft.)	400.00
Type of Mounting	RCC
Tilt Angle	15-22 degrees

Scope of work

1. System sizing/design and engineering. Procurement and supply of projects related material.
2. Civil activities which shall consist of foundation, pedestal and cable conduit fittings.
3. Erection work of module mounting structure.
4. Installation of solar Module, Inverter, Earthing, Lightning Arresters, etc.
5. Complete wiring work related to solar
6. Facilitation of Net-metering inclusive of application processing, meter replacement etc.
7. Commissioning of Plant
8. Operation & Maintenance.

Bill of material

Item	Quantity	Make
Modules (Topcon, Bifacial) DCR 580W	9 nos.	Rayzon Solar/Premier Energy/RenewSys/Pahal/Adani/TATA Power
Modules (Topcon, Bifacial) NDCR 600W	0 nos.	Rayzon Solar/Premier Energy/RenewSys/Pahal/Adani/TATA Power
Inverter	5.00 kW	Growatt/Deye

Bill of material (continued)

Item	Quantity	Make
Mounting Structure	5.00kW	HDGI
DC Cable/AC Cable	As per the requirement	As per MNRE specification
ACDB with surge protection device	1	Sologix
DCDB with Surge Protection Device	1	Sologix
Earthing	3 nos.	Indian Standard Make
Lightning Arrestor	1 no.	Indian Standard Make

- Make and quantity indicated is tentative. It may change as per site condition and product availability.

Commercial Offer

Work Description	Price (Inclusive of GST)
Supply & Installation of ONGRID Solar Plant 5.00kW	₹285,000.00
Online Monitoring System (Wi-Fi)	₹8,000.00
Net Meter Application & Assistance	₹7,000.00
Discount (5.00%)	-₹15,000.00
GRAND TOTAL	₹285,000.00
CFA (DBT after Project is Commissioned)	Rs.78,000

Note:

- Easy approach to the work site to be provided by the consumer.
- Shadow free space on the roof should be provided for the installation of solar panels.
- Sim Data Service for remote monitoring is free for the first year. Thereafter a charge of Rs. 1500 per year.
- The cost of the Raised Structure will be Rs. 5000 per kW.

Payment Terms

Milestone	Amount Payable
Advance payment at order confirmation	Rs. 142,500.00
Payment on delivery of material at site	Rs. 85,500.00
Final payment on commissioning	Rs. 57,000.00

Warranty

- 12 Years warranty on solar modules against manufacturing defects
- 30 Years linear performance guarantee on solar modules
- 8 years warranty on solar on-grid Inverters.

Payment Details

Bank Account Number	125009426214
Bank Account Name	Sologix Energy Private Limited
Bank & Branch	Canara Bank, Chutia, Ranchi, Jharkhand - 834001
RTGS/NEFT IFSC No.	CNRB0001969
No. Permanent Account	AAZCS9296C

UPI Payment

SOLOGIX ENERGY

UPI ID: 8287766474@okbizaxis

Scan & Pay via GPay / Paytm / PhonePe / BHIM UPI

- Details for making payment including in proposal, do not forget to collect receipt of payment.

Acceptance of Proposal

For: Ramesh Kumar Sharma	For: Sologix Energy Private Limited
Sign	Sign
Name:	Name:
Date:	Date:
Address: Plot 45, Sector 2, Harmu Housing Colony, Ranchi, Jharkhand - 834002	Address: 2nd Floor, STPI, Namkum, Ranchi- 834010

Sologix
Energizing Naturally